

ROSELAWN CREMATORIUM Catafalque Handrail

PROVIDE NEW BRASS HANDRAILINGS AND POSTS TO STEPS AND CATAFAQUE SURROUND, ALL TO BS 5395-1, 2010: PART 4.1 AND SET OUT AS DIMENSIONED ON GA DRAWING.

HANDRAILS: 45mm Ø C.H.S.. HANDRAILS TO BE CONTINUOUS,

HANDRAIL TO STEPS TO BE FIXED AT A HEIGHT OF 950mm TO CENTRE OF RAIL ABOVE STEP PITCHLINE, ENDS RETURNED DOWN AND EMBEDDED INTO EXISTING LOWER FLOOR LEVEL AS DESCRIBED BELOW AND GIVING 300mm PROJECTION BEYOND BOTTOM NOSINGS AS SHOWN. HANDRAIL TO CATAFALQUE SURROUND TO BE FIXED AT A HEIGHT OF 1100mm TO TOP OF RAIL FROM UPPER FLOOR LEVEL. POSTS: 45mm Ø C.H.S. POSTS POSITIONED AS SHOWN AND ROOT EMBEDDED AS MANUFACTURER'S RECOMMENDATIONS WITHIN EXISTING FLOOR SCREED/ SLAB. (FLOOR SCREED/ SLAB TO BE CORE DRILLED BY OTHERS AS REQUIRED).

COVER PLATES TO BE PROVIDED TO BASE OF ALL RAILING ABUTMENTS WITH FLOOR. COVER PLATES TO BE BRASS TOP HAT PROFILE, FIXED AS MANUFACTURERS RECOMMENDATIONS.

FINISH: ALL HANDRAIL, UPRIGHTS, COVER PLATES ETC. TO BE BRASS WITH A MIRROR POLISHED FINISH.

ALL JOINTS TO BE WELDED AND SMOOTH FINISHED.

CONSTRUCTION

Revision:	Date:	Detalls:		
			?????	
0			?????	
4	???'??		22222	



Property & Projects Department

Facilities Management Section Property Maintenance Unit Duncrue Complex Duncrue Road Belfast BT3 9BP

BT3 9BP Tel: 028 9032 0202

Site No: 196 Building No: 19601	Site Name: ROSELAWN CEMETERY Building Name: CREMATORIUM		
Project No: 11674565	Project Name: PROPOSED WORKS TO LOWER AND PROVIDE EXTENSION TO CATAFALQUE		
Drawlng No: AS-04	Drawing Name: PROPOSED CATAFALQUE HANDRAIL		
Scale: NOT TO SCALE	Date Drawn: NOV. 2010	Revision:	