

RPII ANNUAL PLAYGROUND INSPECTION REPORT



QUEEN MARY'S WATERWORKS BELFAST CITY COUNCIL 28th April 2014

This Inspection was carried out by Mel Campbell RPII Signed Market Bong full

Site Name: Queen Mary's Waterworks Play Area, Cavehill Road, BT15 5AF

Item No.	Item Description	Inclusive for all Abilities Y/N	Quality Score	Compliance with BSEN 1176 Y/N	User Risk Assessment	Act	ions	Item Priority	Safety Surface Compliance to BSEN 1177	Surfacing Risk Assessment	Actions	Surface Priority Works
1	Item: Multi Unit Manufacturer: Wicksteed Label: No Age Range: 4 + Capacity: 8 Surfacing: Black Tiles	Ν	10	Y	L		Problem: Missing bolt on bridge slat Recommendation Replace	4	Y	L	N/A	5
2	Item: Cradle Swings Manufacturer: Wicksteed Label: Yes 2004 Age Range: 1 - 5 Capacity: 4 Surfacing: Red Wet Pour	Y	2	Ν	М		Problem: 3 missing seats and sets of chains Recommendation Replace Problem: One cradle and chains worn Recommendation Replace	2	Y	L	N/A	5
Overa	II Mean Score =											

* Priority Action3 Action within 28 Days1 Action within 1 Hour (Contact Client)4 Action within 3 months2 Action within 10 Days5 Monitor

Item No.	Item Description	Inclusive for all Abilities Y/N	Quality Score	Compliance with BSEN 1176 Y/N	User Risk Assessment	Ac	tions	Item Priority	Safety Surface Compliance to BSEN 1177	Surfacing Risk Assessment	Actions	Surface Priority Works
3	Item: Rabbit Rocker Manufacturer: Proludic Label: Yes 2007 Age Range: 2 - 8 Capacity: 1 Surfacing: Red Wet Pour	Y	2	Ν	М		Problem: Bolt on seat needs tightened Recommendation Tighten bolt	2	Y	L	N/A	5
4	Item: Dolphin Rocker Manufacturer: Proludic Label: Yes 2007 Age Range: 2 - 8 Capacity: 2 Surfacing: Red Wet Pour	Y	2	Ν	М		Problem: Both side panels rotting Recommendation Repair	2	Y	L	N/A	5
Overa	II Mean Score =		_					l				

* Priority Action3 Action within 28 Days1 Action within 1 Hour (Contact Client)4 Action within 3 months2 Action within 10 Days5 Monitor

Site Name: Queen Mary's Waterworks Play Area, Cavehill Road, BT15 5AF

Date:	28/04/14
-------	----------

Item No.	Item Description	Inclusive for all Abilities Y/N	Quality Score	Compliance with BSEN 1176 Y/N	User Risk Assessment	Ac	tions	Item Priority	Safety Surface Compliance to BSEN 1177	Surfacing Risk Assessment	Actions	Surface Priority Works
5	Item: Flat Swings Manufacturer: Wicksteed Label: No Age Range: 2 - 12 Capacity: 4 Surfacing: Black Tiles	Ζ	2	Ζ	М		Problem: Chains worn by 70% Recommendation Replace worn chains Problem: One seat worn Recommendation Replace Problem: One seat, shackles and chains missing Recommendation Replace	3	Y	L	N/A	5
6	Item: Tyre Swing Manufacturer: Wicksteed Label: No Age Range: 2 - 12 Capacity: 1 Surfacing: Black Wet Pour	Ν	2	Ν	М		Problem: Tyre, chain and shackles missing Recommendation Replace Problem: Bushes worn at rotating section Recommendation Replace	2	Y	L	Repair shrinkage gaps on surface	3
Overa	II Mean Score =											

* Priority Action3 Action within 28 Days1 Action within 1 Hour (Contact Client)4 Action within 3 months2 Action within 10 Days5 Monitor

Item No.	Item Description	Inclusive for all Abilities Y/N	Quality Score	Compliance with BSEN 1176 Y/N	User Risk Assessment	Ac	tions	Item Priority	Safety Surface Compliance to BSEN 1177	Surfacing Risk Assessment	Actions	Surface Priority Works
7	Item: Multi Unit Manufacturer: Sutcliffe Label: No Age Range: 4 + Capacity: 10 Surfacing: Red Wet Pour	Ν	2	Ν	М		Problem: Wear on steps Recommendation Replace 2 steps Problem: Missing rope Recommendation Replace Problem: Wear on rope climber Recommendation Monitor	2	Y	L	N/A	5
Overa	all Mean Score =	3.1										

* **Priority Action** 1 Action within 1 Hour (Contact Client) 2 Action within 10 Days

3 Action within 28 Days4 Action within 3 months 5 Monitor

Site Name: Queen Mary's Waterworks Play Area, Cavehill Road, BT15 5AF

ANCILLARY STRUCTURES

	LARTSTRUCTURES		
TYPE	GENERAL QUALITY CONDITION	ACTIONS	PRIORTY
Boundary Fencing	10	N/A	5
Gates	2	Remove finger entrapment at gate Replace missing rubber buffer Repair damaged hinge	2
Signs	10	N/A	5
Bins	10	N/A	5
Seats/Benches	10	N/A	5
Paths	5	Repair shrinkage gaps at wet pour / kerb edges	3
	OVERALL MEAN SCORE: 7.8		

Action within 1 Hour (Contact Client)3 Action within 28 Days1 Action within 1 Hour (Contact Client)4 Action within 3 months2 Action within 10 Days5 Monitor